

# OTTAWA COUNTY ENGINEERS OFFICE

REFERENCE NO. 1-7-13-F  
EAST QUARTER POST SEC. 1  
ALLEN TWP.  
SHEET 1 OF 1.

ROUTE: C-213 NISSEN RD.

TOWNSHIP: ALLEN

SECTION: 1

T 7 NR 13 E.


**PERSONNEL:**

M. WITTMAN, P.S.  
J. ALLEN  
J. HAYES, BEC ASSOC.  
D. ST. CLAIR, BEC ASSOC.

NORTHING:

EASTING:

DATUM:



**DATE / WEATHER / TEMP:**

MAY 16, 2017  
SUNNY - W-SW  
68° F

MONUMENT INFORMATION

MONUMENT TYPE: FD. POINTED LIMESTONE  
ON SURFACE - BELOW: 0.80'  
LEFT - CL PAV'T - RIGHT: 4.05'

TRIANGULAR SHAPED STONE 9-1/2" X 7"



MISC. INFORMATION

BEC ASSOCIATES STAKED A POINT BASED ON ANGLE AND DISTANCE FROM 1902 DEWITT SURVEY. STONE WAS ON WEST EDGE OF HOLE DUG. 1941 ROAD SURVEY STATED STONE OVER STONE. SET DRILL HOLE IN POINT ON STONE. DRILL HOLE WAS 0.75' WEST AND 0.23' SOUTH OF STAKED POINT.

MAY 16, 2017

SET MONUMENT BOX OVER  
FOUND STONE

