

# OTTAWA COUNTY ENGINEERS OFFICE

REFERENCE NO. 16-7-13-H  
SOUTH QUARTER POST SEC. 16  
ALLEN TWP.  
SHEET 1 OF 1.

ROUTE: C-66 MOLINE-MARTIN RD. @  
C-72 BOLANDER RD.

TOWNSHIP: ALLEN

SECTION: 16

T 7 NR 13 E.

NORTHING:

EASTING:

DATUM:

## PERSONNEL:

M. WITTMAN, P.S.  
J. ALLEN  
C. MILLER, E. KOCH  
T. RAHM, D. BROUGH - GARAGE

## DATE / WEATHER / TEMP:

JULY 13, 2009  
SUNNY  
65° F



## MONUMENT INFORMATION

MONUMENT TYPE: FD HARDHEAD STONE  
ON SURFACE - BELOW: 2.15'  
LEFT - CL PAV'T - RIGHT: 1.55'  
RECTANGULAR STONE: 6" x 4"

USED DEPRESSION IN CENTER OF STONE.



## MISC. INFORMATION

FD. RAILROAD SPIKE 0.35' BELOW SURFACE.  
TIED W/ CROSS TIES AND DUG FOR STONE. FD.  
CONCRETE IN CLAY TILE 1.65' BELOW SURFACE.  
CLAY TILE WAS 3" INSIDE DIAMETER AND 6' TALL  
CENTERED OVER STONE. RAILROAD SPIKE  
WAS 0.09' EAST AND 0.12' SOUTH.

JULY 13, 2009

SET 1" SQUARE IRON PIN  
IN MONUMENT BOX OVER  
STONE

