

# OTTAWA COUNTY ENGINEERS OFFICE

REFERENCE NO. 27-8-13-H  
 SOUTH QUARTER POST SEC. 27  
 ALLEN TWP.  
 SHEET 1 OF 1.

ROUTE: T-70 CURTICE E/W RD.  
 @ T-268 SHORT RD.

TOWNSHIP: ALLEN

SECTION: 27

T 8 NR 13 E.

NORTHING:

EASTING:

DATUM:



**PERSONNEL:**

M. WITTMAN, P.S.  
 J. ALLEN  
 J. RACE  
 K. TOMOR

**DATE / WEATHER / TEMP:**

MAY 31, 2023  
 SUNNY  
 85° F


MONUMENT INFORMATION

MONUMENT TYPE: FD RR SPK IN 3/4" Ø IRON PIPE  
 ON SURFACE - BELOW: 0.35'  
 LEFT - CL PAV'T - RIGHT: 6.05' CURTICE E/W RD  
LEFT - CL PAV'T - RIGHT: 1.97' SHORT RD

IRON PIPE IS MONUMENT OF RECORD

MISC. INFORMATION

FD PONY SPIKE ON SURFACE, SHOT WITH GPS AND  
 DUG FOR IRON PIPE ON RECORD. FD RR SPK 0.35'  
 BELOW SURFACE SHOT WITH GPS AND CONTINUED  
 TO DIG FOR IRON PIPE. RR SPK WAS FOUND SET  
 INSIDE OF IRON PIPE. SURFACE PONY SPIKE WAS  
 0.06' WEST AND 0.17' SOUTH OF RR SPK IN PIPE.



MAY 31, 2023

SET MONUMENT BOX OVER  
 RR SPK IN IRON PIPE

