

OTTAWA COUNTY ENGINEERS OFFICE

REFERENCE NO. 34-7-14-E
 CENTER POST SECTION 34
 BENTON TWP.

SHEET 1 OF 1.

PERSONNEL:
 M. WITTMAN, P.S.
 J. ALLEN

DATE / WEATHER / TEMP:
 MAY 5, 2016
 SUNNY - N
 63° F

ROUTE: T-79 KOLB RD.

TOWNSHIP: BENTON

SECTION: 34

T 7 NR 14 E.

NORTHING:

EASTING:

DATUM:




MONUMENT INFORMATION

MONUMENT TYPE: FD. 9"x9" TRIANGULAR SANDSTONE
 ON SURFACE - BELOW: 0.56'
 LEFT - CL PAV'T - RIGHT: 2.40'

SHALLOW TRIANGULAR SHAPED STONE WITH SLIGHT
 DEPRESSION IN CENTER.

SET DRILL HOLE IN CENTER OF STONE FOR POINT USED.



MISC. INFORMATION

FD. RR SPIKE ON SURFACE, TIED WITH X-TIES AND
 DUG FOR STONE.

SHALLOW STONE, SET DRILL HOLE AND PLACED
 MONUMENT BOX OVER STONE.

RR SPIKE WAS OVER CENTER OF STONE.

MAY 5, 2016

SET DRILL HOLE IN STONE AND
 SET MONUMENT BOX OVER STONE.

SET 5/8" IRON
 PIN w/ OCE CAP
 FOR REF. TIE
 1' N OF EOP

SET 5/8" IRON
 PIN w/ OCE CAP
 FOR REF. TIE
 1' N OF EOP

