

OTTAWA COUNTY ENGINEERS OFFICE

REFERENCE NO. 17-7-15-F
EAST QUARTER POST SEC. 17
CARROLL TWP.
SHEET 1 OF 1.

ROUTE: STATE ROUTE #19
@ C-93 TOUSSIAINT EAST RD.

TOWNSHIP: CARROLL

SECTION: 17

T 7 NR 15 E.

NORTHING:

EASTING:

DATUM:

PERSONNEL:
M. WITTMAN, P.S.
J. ALLEN
E. KOCH

DATE / WEATHER / TEMP:
MARCH 29, 2010
SUNNY
59° F



MONUMENT INFORMATION

MONUMENT TYPE: FD. 6"x7" RECTANGULAR FLAT
TOP LIMESTONE
ON SURFACE - BELOW: 2.00'
LEFT - CL PAV'T - RIGHT: 1.75'

USED CENTER OF STONE



MISC. INFORMATION

FD. ODOT NAIL AND SHINER ON SURFACE WITH 3'-0"
X-TIES. DUG FOR STONE. FD. RR SPK 0.64' BELOW
SURFACE. RR SPK WAS 0.05' SE OF NAIL AND
SHINER. FD. 1" Ø IRON BOLT 0.77' BELOW SURFACE.
BOLT WAS ALSO 0.05' SE OF NAIL AND SHINER.

MARCH 29, 2010

SET 1" SQUARE IRON PIN
IN ROUND ODOT MONUMENT
BOX OVER STONE

