

OTTAWA COUNTY ENGINEERS OFFICE

REFERENCE NO. 18-7-15-C
 NE CORNER POST SECTION 18
 CARROLL TWP.
SHEET 1 OF 1.

ROUTE: T-92 TOUSSAINT PORTAGE RD.

TOWNSHIP: CARROLL

SECTION: 18

T 7 **NR** 15 **E.**

PERSONNEL:

M. WITTMAN, P.S.
 J. BARNES
 A. WEIRICH, P.S. - BEC
 P. SEGAARD, P.S. - BEC

NORTHING:

EASTING:

DATUM:



DATE / WEATHER / TEMP:

MARCH 13, 2007
 SUNNY SW
 56° F

MONUMENT INFORMATION

MONUMENT TYPE: FD LIMESTONE
 ON SURFACE - BELOW: 1.05'
 LEFT - CL PAV'T - RIGHT:
 RECTANGULAR STONE: 6" N-S x 7 1/2" E-W



MISC. INFORMATION

FD 1/2" IRON PIN SET BY D.A. BRUNKHORST IN 1981. FOUND STONE 4 3/4" W AND 1" N OF IRON PIN. SET 1" SQ. IRON PIN OVER STONE. REMOVED 1/2" IRON PIN. SEARCHED FOR STONE / MONUMENTS PER D. GULAU SURVEY DATED 1991 - NOTHING FOUND. SEARCHED FOR STONE PER C. DEWITT SURVEY OF 1903 FOUND NOTHING. E. FRANK SURVEYS OF SECTION 17 AND 18 IN 1874 AND 1880 USE SAME REFERENCE TREES TO ONE COMMON POINT. THIS IS THE COMMON CORNER TO SECTIONS 7,8,17,18.

MARCH 13, 2007

FIBERGLASS WITNESS POST 0.95' N

SET 1" SQUARE IRON PIN
 OVER STONE

