

OTTAWA COUNTY ENGINEERS OFFICE

REFERENCE NO. 19-7-15-G
SW CORNER POST SECTION 19
CARROLL TWP.
SHEET 1 OF 1.

ROUTE: C-23 BENTON-CARROLL RD.

TOWNSHIP: CARROLL

SECTION: 19

T 7 NR 15 E.

PERSONNEL:

M. WITTMAN, P.S.
J. ALLEN
E. KOCH


NORTHING:

EASTING:

DATUM:


DATE / WEATHER / TEMP:

JUNE 30, 2009
OVERCAST W
66° F



MONUMENT INFORMATION

MONUMENT TYPE: SET 1" SQ. IRON PIN IN MON. BOX
ON SURFACE - BELOW:
LEFT - CL PAV'T - RIGHT: 8.00'



MISC. INFORMATION

DUG FOR STONE PER ORIG. GOV. SURVEY DATED 1820 AND SURVEY BY C.E. DEWITT DATED 1901. STONE NOT FOUND. SET POINT HOLDING DEWITT DISTANCE PER 1901 SURVEY AND SET ONLINE BETWEEN NORTHEAST CONER BENTON 25 AND EAST 1/4 POST BENTON 25.

THIS IS A CLOSING CORNER.

JUNE 30, 2009

SET 1" SQUARE IRON PIN
IN MONUMENT BOX

FD. 1" SQ. IP
IN MON. BOX
SE COR. BENTON 25

