

OTTAWA COUNTY ENGINEERS OFFICE

REFERENCE NO. 20-7-15-F
EAST QUARTER POST SEC. 20
CARROLL TWP.
SHEET 1 OF 1.

ROUTE: STATE ROUTE #19
@ T-96 GENZMAN RD.

TOWNSHIP: CARROLL

SECTION: 20

T 7 N R 15 E.

NORTHING:

EASTING:

DATUM:

PERSONNEL:

M. WITTMAN, P.S.
J. ALLEN
S. HUSS - ODOT
M. CANTERBURY - ODOT

DATE / WEATHER / TEMP:

MARCH 28, 2010
SUNNY - SW
47° F



MONUMENT INFORMATION

MONUMENT TYPE: FD. 7-3/4"x4-3/4"x12" POINTED
GRANITE STONE
ON SURFACE - BELOW: 1.68'
LEFT - CL PAV'T - RIGHT: 0.40'

USED HIGH POINT ON STONE



MISC. INFORMATION

FD. STEEL PLATE WITH A GOLF BALL PER COUNTY
RECORDS 0.20' ABOVE STONE. THERE IS AN
ANCHOR STONE ON EAST SIDE OF STONE AND A
CEDAR HUB WAS FOUND 0.20' WEST OF STONE.

MARCH 28, 2010

SET 1" SQUARE IRON PIN
IN ROUND ODOT MONUMENT
BOX OVER STONE

