

OTTAWA COUNTY ENGINEERS OFFICE

REFERENCE NO. 21-7-15-A
NW CORNER POST SEC. 21
CARROLL TWP.
SHEET 1 OF 1.

ROUTE: STATE ROUTE #19

TOWNSHIP: CARROLL

SECTION: 21

T 7 NR 15 E.

PERSONNEL:

M. WITTMAN, P.S.
J. ALLEN
E. KOCH
C. MILLER
R. HUHFER, P.S. - ODOT

NORTHING:

EASTING:

DATE / WEATHER / TEMP:


MARCH 28, 2010
SUNNY - SW
47° F

DATUM:



MONUMENT INFORMATION

MONUMENT TYPE: SET 1" SQ. IRON PIN IN ROUND
ODOT MOUMENT BOX
ON SURFACE - BELOW:
LEFT - CL PAV'T - RIGHT: 2.40'



MISC. INFORMATION

FD. PK NAIL AND SHINER ON SURFACE, TIEDS WITH
2'-0" X-TIES AND DUG FOR STONE. FD. RR SPK WITH
PUNCH MARK 0.45' BELOW SURFACE. RR SPK WAS
0.10' NORTH OF NAIL AND SHINER. DUG TO CLAY
AND PRODDED - STONE NOT FOUND. USED PUNCH
MARK IN RR SPK TO SET 1" SQ. IRON PIN.

MARCH 28, 2010

SET 1" SQUARE IRON PIN IN
ROUND ODOT MONUMENT BOX

