

OTTAWA COUNTY ENGINEERS OFFICE

REFERENCE NO. 25-7-15-1
 SE CORNER POST SEC. 25
 CARROLL TWP.
SHEET 1 OF 1.

ROUTE: C-98 SALEM-CARROLL RD.
 @ C-26 CARROLL-ERIE RD.

TOWNSHIP: CARROLL

SECTION: 25

T 7 NR 15 E.

NORTHING:

EASTING:

DATUM:



PERSONNEL:
 M. WITTMAN, P.S.
 J. ALLEN
 C. MILLER

DATE / WEATHER / TEMP:
 NOVEMBER 9, 2012
 SUNNY
 53° F

MONUMENT INFORMATION

MONUMENT TYPE: FD. HARDHEAD STONE
 ON SURFACE - BELOW: 1.63'
LEFT - CL PAV'T - RIGHT: 3.00'

 6-1/2" x 4" RECTANGULAR STONE

 USED HIGH POINT OF STONE



MISC. INFORMATION

FD. RAILROAD SPIKE 0.21' BELOW SURFACE, TIED
 W/ X-TIES AND DUG FOR STONE. RAILROAD SPIKE
 WAS 0.14' W AND 0.05' S OF HIGH POINT AND WAS
 BARELY OVER ANY PART OF STONE.

NOVEMBER 9, 2012

SET 1" SQUARE IRON PIN
 IN MONUMENT BOX OVER
 STONE

