

# OTTAWA COUNTY ENGINEERS OFFICE

**REFERENCE NO.** 26-7-15-C  
 NE CORNER POST SEC. 26  
 CARROLL TWP.  
**SHEET** 1 OF 1.

**PERSONNEL:**  
 M. WITTMAN, P.S.  
 J. ALLEN

**DATE / WEATHER / TEMP:**  
 MAY 9, 2016  
 OVERCAST  
 54° F

**ROUTE:** T-15 CAMP PERRY WESTERN RD.  
 @ C-104 TOUSSAINT SOUTH RD.

**TOWNSHIP:** CARROLL

**SECTION:** 26

**T** 7 **NR** 15 **E.**

**NORTHING:**

**EASTING:**

**DATUM:**



MONUMENT INFORMATION

MONUMENT TYPE: FD 8" x 4" SANDSTONE  
 ON SURFACE - BELOW: 1.82'  
 LEFT - CL PAV'T - RIGHT: 1.30' (TOUSSAINT SOUTH)  
 LEFT - CL PAV'T - RIGHT: 2.00' (CAMP PERRY WESTERN)  
 FD SANDSTONE W/ DRILL HOLE - USED DRILL HOLE



MISC. INFORMATION

FD 5/8" Ø IRON PIN (IN SPRING) 0.25' BELOW SURFACE, TIED W/ X-TIES AND DUG FOR STONE. IRON PIN IN SPRING WAS BENT TO BE OVER STONE. CENTER OF IRON PIN WAS 0.03' SOUTH AND 0.03' WEST OF DRILL HOLE USED ON STONE.

MAY 9, 2016

SET 1" SQUARE IRON PIN  
 IN MONUMENT BOX OVER  
 STONE

