

OTTAWA COUNTY ENGINEERS OFFICE

REFERENCE NO. 29-7-15-F
EAST QUARTER POST SEC. 29
CARROLL TWP.
SHEET 1 OF 1.

ROUTE: STATE ROUTE #19
@ T-97 BIER RD.

TOWNSHIP: CARROLL

SECTION: 29

T 7 N R 15 E.

PERSONNEL:

M. WITTMAN, P.S.
S. HUSS - ODOT
M. CANTERBURY - ODOT

NORTHING:

EASTING:

DATE / WEATHER / TEMP:

MARCH 30, 2010
SUNNY - S
66° F

DATUM:



MONUMENT INFORMATION

MONUMENT TYPE: FD. 8-1/2"x6" ROUND HARDHEAD
STONE
ON SURFACE - BELOW: 1.51'
LEFT - CL PAV'T - RIGHT: 3.53'

USED CENTER OF STONE



MISC. INFORMATION

FD. ODOT NAIL AND SHINER ON SURFACE WITH 3'-0"
X-TIES. DUG FOR STONE. FD. 1" SQ WOODEN HUB
0.96' BELOW SURFACE WITH BROKEN CLAY TILE ON
ALL SIDES IN PEA GRAVEL. HUB WAS 0.16' E AND
0.08' S OF NAIL AND SHINER. KEPT DIGGING AND
FOUND STONE.

MARCH 30, 2010

SET 1" SQUARE IRON PIN
IN ROUND ODOT MONUMENT
BOX OVER STONE

