

OTTAWA COUNTY ENGINEERS OFFICE

REFERENCE NO. 2-6-13-E
 CENTER POST SEC. 2
 CLAY TWP.
 SHEET 1 OF 1.

ROUTE: T-56 FULKERT RD.
 TOWNSHIP: CLAY
 SECTION: 2
 T 6 NR 13 E.


PERSONNEL:
 M. WITTMAN, P.S.
 J. ALLEN

NORTHING:

EASTING:

DATE / WEATHER / TEMP:
 NOVEMBER 30, 2012
 PTLY SUNNY
 40° F

DATUM:



MONUMENT INFORMATION

MONUMENT TYPE: FD. 1" Ø CRIMPED IRON PIPE
 ON SURFACE - BELOW: 0.72'
 LEFT - CL PAV'T - RIGHT:



MISC. INFORMATION

FD. 1" Ø CRIMPED IRON PIPE 0.72' BELOW SURFACE, TIED W/
 X-TIES AND DUG FOR STONE. FD. 9"x15"x12" LIMESTONE
 BROKEN INTO 3 PIECES- 2 SOUTH AND 1 LARGE NORTH OF PIPE.
 SOUTH EDGE OF NORTH STONE MATCHED NORTH EDGE OF
 SOUTH STONE. ONE OF THE PIECES HAS BEEN ROLLED OUT OF
 ALIGNMENT. USED CRIMPED IRON PIPE WHICH WAS DRIVEN
 BETWEEN THE PIECES SET BY C.A. STEVENSON IN 1959.

NOVEMBER 30, 2012

SET MONUMENT BOX OVER
 1" Ø IRON PIPE

