

# OTTAWA COUNTY ENGINEERS OFFICE

**REFERENCE NO.** 27-7-13-B  
 NORTH QUARTER POST SEC. 27  
 CLAY TWP.

**SHEET** 1 OF 1.

**PERSONNEL:**  
 M. WITTMAN, P.S.  
 J. ALLEN

**DATE / WEATHER / TEMP:**  
 DECEMBER 1, 2009  
 SUNNY  
 40° F

**ROUTE:** T-65 HELLWIG RD.

**TOWNSHIP:** CLAY

**SECTION:** 27

**T** 7 **NR** 13 **E.**

**NORTHING:**

**EASTING:**

**DATUM:**



### MONUMENT INFORMATION

MONUMENT TYPE: 9"x7" TRIANGULAR STONE  
 ON SURFACE - BELOW: 0.90'  
 LEFT - CL PAV'T - RIGHT: 3.60'



### MISC. INFORMATION

FD. 3/4" x 8" IRON PIN 0.17' BELOW SURFACE. TIED WITH X-TIES AND DUG FOR STONE. STONE HAD DIMPLE IN TOP CENTER. USED DIMPLE AS 3/4" IRON PIN WAS A SLANT PIN NEAR THE DIMPLE. TOP OF IRON PIN WAS 0.08'S AND 0.03' EOF DIMPLE IN STONE.

DECEMBER 1, 2009

SET 1" SQUARE IRON PIN  
 IN MONUMENT BOX OVER  
 STONE

