

OTTAWA COUNTY ENGINEERS OFFICE

REFERENCE NO. 3-6-13-F
EAST QUARTER POST SEC. 3
CLAY TWP.
SHEET 1 OF 1.

ROUTE: T-7 MARTIN-WILLISTON RD.
@ T-56 FULKERT RD.

TOWNSHIP: CLAY

SECTION: 3

T 6 NR 13 E.


NORTHING:

EASTING:

DATUM:

PERSONNEL:
M. WITTMAN, P.S.
J. ALLEN

DATE / WEATHER / TEMP:
NOVEMBER 29, 2012
SUNNY - SW
38° F



MONUMENT INFORMATION

MONUMENT TYPE: FD. 7/8" HEX DRILL BIT
ON SURFACE - BELOW: 0.73'
LEFT - CL PAV'T - RIGHT: 0.60'

DRILL BIT PER COUNTY RECORDS



MISC. INFORMATION

FD. PK NAIL 0.05' BELOW SURFACE, TIED W/ X-TIES
AND DUG. FD. 7/8" HEX DRILL BIT W/ HOLE 0.73'
BELOW SURFACE. HEX BIT WAS 0.09' E AND 0.03' N
OF PK NAIL. TIED DRILL BIT W/ X-TIES AND DUG FOR
STONE PER 1939 WPA BOOK. DUG TO CLAY AND
PRODDED AROUND DRILL BIT ANOTHER 3' DOWN
AND FOUND NOTHING, DRILL BIT WAS STILL SOLID.

NOVEMBER 29, 2012

MONUMENT BOX OVER 7/8"
HEX DRILL BIT

