

OTTAWA COUNTY ENGINEERS OFFICE

REFERENCE NO. 13-6-13-B
 NORTH QUARTER POST SEC. 13
 HARRIS TWP.
 SHEET 1 OF 1.

ROUTE: T-50 WITTY RD.

TOWNSHIP: HARRIS

SECTION: 13

T 6 NR 13 E.

PERSONNEL:

M. WITTMAN, P.S.
 J. ALLEN
 B. BRADY
 M. HEINTZ

NORTHING:

EASTING:

DATUM:



DATE / WEATHER / TEMP:

APRIL 30, 2024
 SUNNY W-SW
 65° F

MONUMENT INFORMATION

MONUMENT TYPE: FD. POINTED SANDSTONE
 ON SURFACE - BELOW: 1.25'
LEFT - CL PAV'T - RIGHT: 0.90'

FD. 5-1/2" X 7" POINTED LIMESTONE

USED POINT ON STONE



MISC. INFORMATION

FD. MAG SPIKE ON SURFACE, TIED W/ GPS AND DUG FOR STONE OF RECORD. USED HIGH POINT ON STONE WHICH MATCHED RECORD DISTANCE OF 56.15' TO A FD. IRON PIN TO THE EAST. SET 1" SQUARE IRON PIN IN MONUMENT BOX OVER HIGH POINT OF STONE. FD. MAG SPIKE WAS 0.13' EAST AND 0.03' NORTH OF POINT USED ON STONE.

APRIL 30, 2024

SET 1" SQUARE IRON PIN
 IN MONUMENT BOX OVER
 STONE

