

OTTAWA COUNTY ENGINEERS OFFICE

REFERENCE NO. 13-6-14-A
NW CORNER POST SECTION 13
HARRIS TWP.

SHEET 1 OF 1.

PERSONNEL:

M. WITTMAN, P.S.
J. ALLEN
E. KOCH
C. MILLER

DATE / WEATHER / TEMP:

JULY 2, 2009
OVERCAST W
64° F

ROUTE: T-43 SLEMMER-PORTAGE RD.

TOWNSHIP: HARRIS

SECTION: 13

T 6 NR 14 E.

NORTHING:

EASTING:

DATUM:



MONUMENT INFORMATION

MONUMENT TYPE: FD LIMESTONE W/ FAINT "X"
ON SURFACE - BELOW: 1.30'
LEFT - CL PAV'T - RIGHT: 1.45'
RECTANGULAR STONE: 6" x 6"

USED "X" IN STONE.



MISC. INFORMATION

FD. MAG NAIL 0.02' BELOW SURFACE. TIED W/
CROSS TIES. DUG FOR STONE. STONE WAS
COVERED BY SCARP IRON AND PIECES OF
CLAY TILE.

MGA NAIL WAS 0.02' EAST OF "X".

JULY 2, 2009

SET 1" SQUARE IRON PIN
IN MONUMENT BOX OVER
STONE

