

OTTAWA COUNTY ENGINEERS OFFICE

REFERENCE NO. 5-6-14-1
SE CORNER SECTION 5
HARRIS TWP.
SHEET 1 OF 1.

ROUTE: T-19 GRAYTOWN RD.

TOWNSHIP: HARRIS

SECTION: 5

T 6 NR 14 E.

PERSONNEL:

M. WITTMAN, P.S.
J. ALLEN
M. ULLRICH
S. ULLRICH

NORTHING:

EASTING:

DATUM:



DATE / WEATHER / TEMP:

JULY 10, 2008
SUNNY S
80° F

MONUMENT INFORMATION

MONUMENT TYPE: FD. 6" X 8" POINTED
LIMESTONE W/ NORTH -SOUTH NOTCH ON HIGH
POINT
ON SURFACE - BELOW: 1.45'
LEFT - CL PAV'T - RIGHT: 5.45'



MISC. INFORMATION

FD. RR SPIKE 0.30' BELOW SURFACE, TIED IT
DOWN W/ X-TIES: DUG FOR STONE, FD. RR
SPIKE 0.86' UNDER ORIGINAL RR SPIKE.
CONTINUED DOWN TO STONE. RR SPIKE 0.12'
NE OF POINT ON STONE

JULY 10, 2008

SET 1" SQUARE IRON PIN
IN MONUMENT BOX OVER
STONE

