

OTTAWA COUNTY ENGINEERS OFFICE

REFERENCE NO. 23-6-15-F
 EAST QUARTER POST SEC. 23
 SALEM TWP.

SHEET 1 OF 1.

PERSONNEL:
 M. WITTMAN, P.S.
 J. ALLEN

DATE / WEATHER / TEMP:
 APRIL 22, 2014
 SUNNY - NW
 60° F

ROUTE: C-113 BOYSEN RD.
 @ C-36 MUD CREEK RD.
 @ T-217 MUDDY CREEK N. RD.

TOWNSHIP: SALEM

SECTION: 23

T 6 **NR** 15 **E.**

NORTHING:


EASTING:

DATUM:



MONUMENT INFORMATION

MONUMENT TYPE: SET 5/8" Ø IRON PIN IN MON BOX
ON SURFACE - BELOW:
 LEFT - CL PAV'T - RIGHT: 12.20' SOUTH, 32.55' NORTH



MISC. INFORMATION

FD PK NAIL ON SURFACE WITH 2' TIES S,W & E. TIED WITH X-TIES AND DUG FOR STONE PER 1936 WPA NOTES. DUG DOWN 24" TO CLAY, PRODDED ANOTHER 2-1/2' INTO CLAY AND DID NOT FIND STONE. PK NAIL REFERENCED IN MANY SURVEYS ON FILE IN COUNTY ENGINEER'S OFFICE. ACCEPTED PK NAIL AS POINT AND SET 5/8" Ø IRON PIN IN MONUMENT BOX.

APRIL 22, 2014

SET 5/8" Ø IRON PIN
 IN MONUMENT BOX

