

# OTTAWA COUNTY ENGINEERS OFFICE

REFERENCE NO. 33-7-15-B  
 NORTH QUARTER POST SEC. 33  
 SALEM TWP.  
 SHEET 1 OF 1.

ROUTE: C-98 SALEM-CARROLL RD.

TOWNSHIP: SALEM

SECTION: 33

T 7 NR 15 E.

**PERSONNEL:**

M. WITTMAN, P.S.  
 J. ALLEN  
 E. KOCH  
 C. MILLER

NORTHING:

EASTING:

DATUM:



**DATE / WEATHER / TEMP:**

AUGUST 11, 2009  
 OVERCAST HUMID  
 74° F

MONUMENT INFORMATION

MONUMENT TYPE: FD POINTED HARDHEAD STONE  
 ON SURFACE - BELOW: 1.32'  
 LEFT - CL PAV'T - RIGHT: 2.00'  
 TRIANGULAR STONE: 9 3/4" x 4 1/2"  
  
 USED CENTER OF HIGH RIDGE.



MISC. INFORMATION

FD 1" HITCH PIN 0.44' BELOW SURFACE. TIED W/ CROSS TIES AND DUG FOR STONE. FD 1" Ø IRON PIN 1.16' BELOW SURFACE. IRON PIN ON SOUTH SIDE OF STONE MARKING C/L OF HIGH RIDGE OF STONE. PIN HAD SLANT TO NORTH. IT IS BELIEVED THAT PIN WAS ORIGINALLY SLANTED NORTH OVER THE CENTER OF STONE AND HAS SINCE BEEN DRIVEN DOWN. HITCH PIN WAS OVER IRON PIN AND 0.22' SOUTH OF CENTER OF STONE.

AUGUST 11, 2009

SET 1" SQUARE IRON PIN  
 IN MONUMENT BOX OVER  
 STONE

