

OTTAWA COUNTY ENGINEERS OFFICE

REFERENCE NO. 34-7-15-E
 CENTER POST SECTION 34
 SALEM TWP.
 SHEET 1 OF 1.

ROUTE:
 TOWNSHIP: SALEM
 SECTION: 34
 T 7 NR 15 E.

PERSONNEL:
 M. WITTMAN, P.S.
 A. WEIRICH, P.S - BEC ASSOC.

NORTHING: 677087.68
 EASTING: 1799792.61
 DATUM: ODOT VRS (NAD83) 2011



DATE / WEATHER / TEMP:
 OCTOBER 20, 2017
 SUNNY
 60° F

MONUMENT INFORMATION

MONUMENT TYPE: FD SANDSTONE
ON SURFACE - BELOW:
 LEFT - CL PAV'T - RIGHT:
 SANDSTONE IS 4" X 10" X 24" AND TOP IS EXPOSED.
 USED CENTER OF STONE.
 SET DELINEATOR 1.00' WEST OF STONE.



MISC. INFORMATION

STONE FD BY BEC ASSOC. ON 10-19-2017. STONE PREVIOUSLY DEEMED CENTER OF SECTION BY D.A. BRUNKHORST IN SURVEY 1-3-1983. STONE HAS SLIGHT NW / SE ORIENTATION. OLD WIRE FENCE WITH REMNANTS OF WOODEN FENCE POSTS TO THE NORTH AND WEST OF THIS STONE AND ALSO FD 2 STEEL FENCE POSTS (NO WIRE FENCE FD) EAST AT 15 FOOT INTERVALS. MATCHES DESCRIPTION OF STONE IN W.P.A. BOOK 2 PAGE 1. COORDINATES LISTED WERE PROVIDED BY BEC ASSOCIATES, INC. ON 10-20-2017.

OCTOBER 20, 2017

SET DELINEATOR 1.00' WEST OF STONE

